

GENERAL NOTES

1. SEE SHEET M001 FOR NOTES, SCHEDULES, AND SYMBOLS.
2. PROVIDE AIR VOLUME DAMPER AT ALL SUPPLY AND RETURN AIR TAKE-OFF.

SPECIFIC NOTES

1. PROVIDE DUCT SMOKE DETECTOR IN MAIN SUPPLY AND RETURN AIR DUCT.
2. PROVIDE AND INSTALL WALL MOUNTED THERMOSTAT @ R.F.F.
3. PROVIDE INSULATED REFRIGERANT PIPING. ROOM MOUNTED CONDENSING UNIT OUT TO CORNER SHIPMENT COURTESY OF SUPPLIER. INSTALLATION OF UNIT, PROVIDE CONDENSATE DRAIN AND CONNECT TO NEAREST STORM DRAIN.
4. PROVIDE 2-HR RATED ENCLOSURE FOR DUCT PASSING OVER ELECTRICAL ROOM.
5. MINIMUM OF 500 CFM.
6. PROVIDE CEILING FAN MOUNTED 12 FT. AFF.

